Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone
SCHEDULE-B

Tender Notification No:bbmp/DZ/EE(ele)Tn/01/2016-17 **Date :24.06.2016**

Name of the Work:- Providing Repairs and replacement of damaged lighting systems in Parks at dasarahalli Zone.

Sl. No.	Description	Unit	Approved Qty	Approved Rates	
				in Figures	Amount in in words
1	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanished, steel wire/steel tap armoured cable with PVC outer sheating 1.1 KV class.I. Class 'A' PVC Cable. 4 core 16 sqmm	Per Mtr	400	130.00	Rupees One Hundred and Thirty Only
2	Labour charges for lying of 1.1 KV class UG cable when supplied agency in existing trench Gl pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct.b)25sqmm to 75 sqmm	Per Mtr	400	14.00	Rupees Fourteen Only
3	Digging of trench of 0.6 m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc.,complete. (As perCivil SR KSRB l-2, P-7).a) In soil (ordinary)	Per Mtr	360	78.00	Rupees Seventy Eight Only
4	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.f)40-63Amps TPN, Group A	Each	5	1800.00	Rupees One Thousand Eight Hundred Only
5	5-32Amps SP	Each	10	410.00	Rupees Four Hundred and Ten Only
6	Supplying and fixing electro mechanical timer (without contactor) using necessary bolts, nuts and washers etc.. Group A, PWD SR 2006-07,	Each	5	3800.00	Rupees Three Thousand Eight Hundred Only
7	Supply and fixing of 4-pole power contactor with NO/NC contacts on existing wood / panel board using necessary bolts, nuts, washers and wiring etc., complete. d) 100-125 Amps	Each	5	9400.00	Rupees Nine Thousand Four Hundred Only
8	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and **Copper** conductor single core cable in open or consealed system of wiring.I Group A Materials.g)16 sqmm	Per Mtr	30	130.00	Rupees One Hundred and Thirty Only
9	Supplying and fixing phylum brand hand plastic sheet 3mm thick with necessary niches for fixing switches, regulators etc., and fixing on exisiting wood or metal box using	Sqcm	11000	0.22	Rupees Zero Only Paise Twenty Two Only
10	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. And M.S. flat… with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. a)40X40X6mm	Per Mtr	18	200.00	Rupees Two Hundred Only
11	Fabricating supplying and mounting MS box made out… SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size cdlamps with mecessary cable entry pipe with gland and box should be finished with 2 cdoats of red oxide primer paint and finally finished with approved colour enameled metal pain etc., complete. b)16 swg	Sqcm	135000	0.33	Rupees Zero Only Paise Thirty Three Only
12	Fixing halogen/ metal hallide /SVL/IL/LED flood light fittings over existing pole/ wall ceiling including clamps bolts nuts and wiring using sitable capacity wires	Each	39	150.00	Rupees One Hundred and Fifty Only
13	Supplying 70Watts MH integral post top lantern Metal halide fitting suitable for pole mounted with fully vermin, weather proof, elegant in shape, appearance, UV stabilized clear acrylic diffusers, camouflaged horizontal lamp, holder and lamp, IP 54 protection. Electrical safety class 1. The fitting shall have ferromagnetic copper choke with capacitor, igniter and fully wired to operate on 230V 50Hz AC Supply with 70Watts MH Lamp.	Each	39	6400.00	Rupees Six Thousand Four Hundred Only

I am prepared to take up the above work at the rates quoted in the Schedule 'B'

CONTRACTOR

3/3/16

Executive Engineer(Ele)
BBMP, Dasarahalli Zone